



भा.कृ.अनु.प. - राष्ट्रीय अनार अनुसंधान केन्द्र, सोलापूर  
ICAR-NATIONAL RESEARCH CENTRE ON POMEGRANATE  
(Indian Council of Agricultural Research)

NH-9 Solapur-Pune Highway, Kegaon, Solapur-413 255 (M.S.) India  
Tel: 0217-2354330, 2350074, 2350263, Fax: 0217-2353533, 0217-2350262 (Director)

E Mail: [nrcpomgranate@gmail.com](mailto:nrcpomgranate@gmail.com), [director@nrcpomgranate.org](mailto:director@nrcpomgranate.org),  
[contact@nrcpomgranate.org](mailto:contact@nrcpomgranate.org), [rkrishnapal@gmail.com](mailto:rkrishnapal@gmail.com)

Website: [www.nrcpomgranate.org](http://www.nrcpomgranate.org)

(ISO 9001:2008 Certified Institute)



F. No. 5-60/Leakages & waterproofing work /Store/15

Dated: 09.04.2015

To

Sub: Notice Inviting Quotations (NIQ) for Repair of leakages and waterproofing work, fixing new door at terrace, providing kota flooring at post harvest lab and removal of old and fixing of new tiles over the porch both side at NRCP, Solapur – reg.

Sir,

Quotations are invited for Repair of leakages and waterproofing work, fixing new door at terrace, providing kota flooring at post harvest lab and removal of old and fixing of new tiles over the porch both side at NRCP, Solapur as per details INDICATED in the Schedule of Requirements for use in the NRC on Pomegranate, Solapur. You are requested to submit your quotation immediately. We seek timely completion of required work as per schedule of requirement with good quality material and most competitive rates. The following terms and conditions will govern for above said item of work.

**TERMS & CONDITIONS:**

1. The **Registered Contractors** are eligible to submit the quotation. A copy of their Registration should be enclosed with the Quotation.
2. The Contractor is requested to submit their quotation for the above said work on or before **30.04.2015**
3. Contractors should personally visit the working site/ area, before quoting their rates to understand the accurate requirement of this Centre.
4. **EMD:** An amount of Rs.5,000/- (Rupees Five thousand only) in the form of Demand Draft drawn in favour of "ICAR Unit: NRC on Pomegranate" will have to be submitted along with the quotation.

**Quotations received without EMD will not be considered at all.**

**EMD in full will be refunded soon after the quotations are finalized to all except in case of the accepted quotation.**

The EMD of the accepted quotation will be refunded only after full and satisfactory completion of work.

5. **Due Date:** Quotations received after due date will not be considered. Centre will not be responsible for postal delays.
6. **Submission:** Quotation with proper superscription on the cover should be submitted in the Office of the Director, NRCP, Solapur on or before the due date.

7. **Payment:** No advance payment will be made. Payment shall be made on bill basis only after satisfactory completion of the work within schedule time after receipt of bill in duplicate.
8. This Centre will not provide any labour assistance in carrying out the said contract work.
9. The Contractor should arrange the labour and also tools, implements etc. needed by the labour to carry out the work.
10. The contractor should get verified by the concerned officer about the quality of material being used in the said work.
11. The **Income Tax on prevailing** rate will be deducted from the bill amount as per the provision of TDS
12. Responsibility: The Centre shall not be responsible and not be liable to pay any compensation for any loss, damage, etc. caused by the actions by the contractor or by the persons employed by them in performing this contract. The Centre does not take any responsibility and should not be held liable for any damage to labour employed by the contractor.
13. **Carryout the work:** Contractor has to inform the concerned Officer before starting the work and the allotted work as per contract has to be carried out in the presence of concerned officer of this Centre.
14. Work should be carried out as per specification mentioned in schedule of work and sketch/ drawing enclosed herewith.
15. Good/Standard quality material should be used for construction.
16. The **work contract agreement** should be entered with this Centre before commencement of the work.

Yours faithfully,

Encl: Schedule of Requirement

(A. A. Goswami)  
ADMINISTRATIVE OFFICER

**Annexure -I**

**Schedule of Requirement**

(To be typed/printed on the letterhead of the tender)

**Last date for Receipt of quotation: 30.04.2015**

**Name of Work:** Repair to leakages and waterproofing work, at NRCP Solapur

<b>Item No.</b>	<b>Description of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount (Rs.)</b>
1.	Dismantling the existing waterproofing B. B. Coba and side wall plaster to identify the leakages		Job Work		
2.	Water proof treatment:- Applying three coats of polymer like Hydro proof to the slab and providing and laying brick bat coba in C.M. 1:3 with waterproof plaster to the side walls and changing the P trap if necessary under the supervision of engineer incharge and as directed complete		Job Work		
3.	Providing and laying the granite stone flooring as directed by Engineer incharge including polishing etc. complete	3.5	Sqm.		

(Rupees: \_\_\_\_\_)

**Schedule of Requirement**

(To be typed/printed on the letterhead of the tender)

**Last date for Receipt of quotation: 30.04.2015**

**Name of Work:** Fixing new terrace doors, at NRCP Solapur

<b>Item No.</b>	<b>Description of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount (Rs.)</b>
1.	Providing and fixing waterproof and resistant to atmospheric changes doors at terrace, including fixtures and fastenings etc. complete	02 Nos	No.		

(Rupees:\_\_\_\_\_

**Schedule of Requirement**

(To be typed/printed on the letterhead of the tender)

**Last date for Receipt of quotation: 30.04.2015**

**Name of Work:** Providing kotah flooring at post harvest lab, at NRCP Solapur

<b>Item No.</b>	<b>Description of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount (Rs.)</b>
1.	Removing and dismantling the B. B. coba and stacking the material as directed and preparing the surface for kotach flooring		Job work		
2.	Providing and laying kota stone slab flooring 25 to 30 mm thick over 40 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1:4 (1 cement : 4 coarse sand) : as directed by engineer incharge	23.23	Sqm.		

(Rupees: \_\_\_\_\_)

**Schedule of Requirement**

(To be typed/printed on the letterhead of the tender)

**Last date for Receipt of quotation: 30.04.2015**

**Name of Work:** Granite cladding for porch, at NRCP Solapur

<b>Item No.</b>	<b>Description of Items</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount (Rs.)</b>
1.	Removing the existing granite tiles at entrance porch and preparing the surface for receiving the new tiles, including scaffolding and stacking the material as directed and as per the instructions of Engineer Incharge		Job work		
2.	Providing and fixing the cladding of granite tiles as approved by Engineer Incharge at entrance porch sides using bonding chemical, cement and colour pigment as directed, including polishing, scaffolding, curing etc. complete	27	Sqm.		

(Rupees: \_\_\_\_\_)

Note: **The quotations received without EMD will not be considered.**

Signature: \_\_\_\_\_

Name: \_\_\_\_\_

Designation: \_\_\_\_\_

Name of bidder: \_\_\_\_\_

Place:

Address: \_\_\_\_\_