



भा.कृ.अनु.प.- राष्ट्रीय अनार अनुसंधान केन्द्र, सोलापुर  
ICAR - National Research Centre on Pomegranate

(Indian Council of Agricultural Research)

NH-65, Solapur-Pune Highway, Kegaon, Solapur-413 255 (M.S.)

T-(0217) 2354330, 2350074, 2350263, F-(0217) 2353533

E mail- nrcpomegranate@gmail.com, Website- nrcpomegranate.icar.gov.in

(ISO 9001:2015 Certified Institute)



F. No. 57-15/DG Set/RKVY/BCL/23

Dated: 03.10.2024

**TECHNICAL SPECIFICATION CORRIGENDUM**

With reference to this office tender/bid vide no. GEM/2024/B/5390370 dated 12.09.2024 for supply and installation of DG Set, it is to inform that the Technical Specification mentioned at point no. 2 and 9 of Annexure-I of the tender document must be read as follows:

Sl. No.	Specification Name	Existing Requirement/Specification	Modified Requirement/Specification
2.	Nominal Rated Capacity (kVA)	60 to 65 KVA	55-60 KVA, BS-IV as per CPCB+ Norms
9.	Installation	With installation - inclusive in the scope of supply born by the supplier • Foundation and earthings. • Power and control cabling required for Cable connection from the DG set to the distribution panel (approx. 120-140 meters), including unloading, labour, and machine work for pit digging to a depth 60-90cm for approximately 90-100 meters.	With installation - inclusive in the scope of supply born by the supplier • Foundation and earthings. • Power and control cabling required for Cable connection from the DG set to the distribution panel (approx. 120-140 meters), including unloading, labour, and machine work for pit digging to a depth 60-90cm for approximately 90-100 meters. • Cable Encloser: Double walled corrugated HDPE Pipe as encloser for power and control cable

This is issued with the approval of the Director, ICAR-NRCP, Solapur.

  
**ADMINISTRATIVE OFFICER**